

**Addendum #3 RFI Responses**

**To:** All Possible Proposal Submitters

**From:** FinePoint Technology, LLC; Legislative Coordinating Commission (LCC)

**Project:** Minnesota Legislature Television System Acquisition Project – MN State Office Building Equipment Phase 2

Legislative Coordinating Commission

**Date:** May 7, 2026

**Re:** Addendum #3 RFI Responses

---

This Addendum forms a part of and modifies previously issued Contract Documents as indicated below or by attachments. Bidders must acknowledge receipt of this Addendum. Failure to do so may subject the Bidder to disqualification. Drawings and Specification references made below are a general guide only. Bidder must determine for themselves the Work affected by Addendum items.

---

**Instructions/Description/References/Dates**

---

**SPECIFICATIONS**

1. RFP Legislative Media Project Phase 2 – Addendum 3
  - a. Revisions indicated
2. Section 27 41 16 – Broadcast System Bill of Materials Phase 2 v3 Addendum 3
  - a. Revisions indicated
3. Section 27 41 16 – Broadcast System Specifications Phase 2 Addendum 3
  - a. Revisions indicated

**QUESTIONS**

1. CAN WE CHANGE ORX1702-1 TO LC FROM ST?
    - a. **[LCC Response] LC version is acceptable. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.JJ.8)**
  2. ALIF101T-HDMI IS DISCONTINUED
    - a. **[LCC Response] For [KVM-TX-1], provide Adder ALIF102T-HM or -DP; or Adder ALIF101T-DVI; or Adder ALIF100T-VGA. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.P.10.e.1)**
  3. CALL OUT FOR ICMTX BUT THIS DOES NOT EXIST IN BOM, WHAT IS THE DEVICE REQUIRED
    - a. **[LCC Response] [ICMTX-1] is required in SOB 0G125 Equipment Room. (Refer to revised Bill of Materials Addendum 3, line 186)**
  4. ARE THERE 2 SWITCHER PANELS IN CNTL RM 1-0G123? SHOWN ON DRAWING, BUT NOT IN BOM
    - a. **[LCC Response] [LCC Response] One [SWCP-2S] is required in SOB 0G123 PCR 1. (Refer to revised Bill of Materials Addendum 2, line 139). The specified [SWCP-2S] contains both a switcher panel and touch screen, indicated by separate callouts in the drawings. (Refer to House Broadcast Systems Concept and Functional Drawings, B302.1)**
-

5. THERE ARE 8030C AND 8010A IN THE CNTRL RM WITH ONLY ONE VCP-2, DOES THIS CONTROL BOTH OR DOES THE SOLUTION REQUIRE AN ADDITIONAL VCP?
  - a. **[LCC Response] Control Room program monitors [SPK-2] are controlled via [VCP-2] connected to [AMIX-1]. Control room cue monitors [SPK-3] are connected to and controlled by [AMIX-1] directly using the cue select and cue volume functions. (Refer to House Broadcast Systems Concept and Functional Drawings, B402.11)**
6. STUDIO PLATES, SDI COUNTS TO AND FROM THE ROUTER? AUDIO 8 IN, 4 OUT?
  - a. **[LCC Response] [PLT-STUDIO-1] cabling from plates in SOB 0G102 Studio is landed to patch panels in SOB 0G125 Equipment Room. (Refer to House Broadcast Systems Concept and Functional Drawings, B402.26)**
7. WHY DO YOU HAVE A WHOLER AND TSL IN THE SAME RACK FOR AUDIO MONITORING?
  - a. **[LCC Response] [AMON-1] and [AMON-2] are used for general signal quality control and inspection. [AMON-3] provides knob-per-room audio monitoring of every hearing room and control room program, allowing users to mix and monitor multiple hearings simultaneously with user-friendly volume control for each signal.**
8. MICE ARE MISSING FROM BOM, WHICH DEVICE ARE YOU LOOKING FOR
  - a. **[LCC Response] See [KB-1]. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.P.1)**
9. in the design documents you show 6x Netswitch-1, in the BOM there are only 2. are all the qsfps in the ofoi equipment supplied to make the solution work or does the SI need to do a forensic to validate that these need to be included in the response
  - a. **[LCC Response] [NETSW-1], quantity 2, are required in SOB 0G125 Equipment Room. They will be integrated with [NETSW-1], quantity 2, in CAP and [NETSW-1], quantity 2, in MSB. Contractor to provide all [SFP-xx] optics for connections to OFOI networks. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.Y; §2.04.B )**
10. VMON 5 DOES NOT FIT INTO A RACK AND IS NOT SHOWN ON ELEVATIONS
  - a. **[LCC Response] [VMON-5] is not required to be rack-mounted within this design.**
11. KMON-2 WILL NOT FIT SIDE BY SIDE IN RACK 24.1" WIDE, CAN WE SUBSTITUTE THESE?
  - a. **[LCC Response] [KMON-2] can be mounted side-by-side, proud of the front of the rack, using a short-articulated rack mount. They are currently mounted in this configuration in CAP Media Hub and MSB Equipment Rack Room.**
12. IS THERE A NEED FOR 2X RCP-1 IN RACKS BER-02 AND BER-03?
  - a. **[LCC Response] Yes. One is a typical router XY panel, and the other shows a custom Air Chain monitoring panel already developed by Ross Video Rocket Surgery. Minor modifications to incorporate the SOB into that custom panel software are covered under OEM Professional Services. (Refer to revised 27 41 16 Specifications Addendum 3, §2.07.B)**
13. BLACKMAGIC QUAD IS NO LONGER AVAILABLE, REPLACE WITH 8K PRO G2
  - a. **[LCC Response] [UPC-3] and [UPC-4] specify Blackmagic DeckLink Quad 2 cards, which are active and supported. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.NN.3-4)**
14. FDR-6604-R2 IS NOT LONGER AVAILABLE, USE SFC-6901-R3F?
  - a. **[LCC Response] "FDR-6604-R2" is not specified in this project.**
15. CABLE REQUIREMENT COAX: 3G OR 12G THROUGHOUT THE FACILITY? It states both in the spec but the common video spec is 1080p 59.94.
  - a. **[LCC Response] 3G-SDI cabling is acceptable throughout the facility. The only 12G-SDI requirement is for Control Room wall multiview displays, should the Contractor choose to install copper rather than singlemode fiber to those displays.**
16. CCP-1 requests a Cyanview CY-RCP-J. How many licenses are required for each Cyanview CY-RCP-J?

- a. [LCC Response] All [CCP-1] connect to a single [CCP-2], which shall be capable of controlling all cameras within the SOB & CAP.**
17. In the Capital Building Drawings, Sheet B201.9, [PLT-Studio-1] is indicated as OFOI. On the Bill of Materials, this plate is not indicated as OFOI. Is this the same plate or a new plate?
- a. [LCC Response] [PLT-STUDIO-1] in CAP 242 House Chambers Gallery is OFOI. Bill of Materials revised to reflect this designation. (Refer to revised Bill of Materials Addendum 3, line 516)**
18. Are pathways already provided in the Capital building for adding the additional I/O?
- a. [LCC Response] Pathways are provided.**
19. LTO-1 on page 65 of the specifications document is referenced as OFCI. On the Bill of Materials, it is not referenced as OFCI. Is LTO-1 OFCI or CFCI?
- a. [LCC Response] [LTO-1] is OFCI. Bill of Materials revised to reflect this designation. (Refer to revised Bill of Materials Addendum 3, line 227) The Owner may elect, in a future change order, to remove [LTO-1] and use [ALLOW-SOB-LTO] to purchase a new LTO device.**
20. In section 2.04.A.1.a, the closed captioning equipment is notated as OFCI. That same subsection asks to provide 3G-SDI Level A/B conversion. Sheet B402.22 of the House-Broadcast document shows CC-1 as OFCI, however, the notation in the drawings does not show the 3G Level A/B Conversion as OFCI. Do we need to provide 3G-SDI Level A/B conversion?
- a. [LCC Response] [CC-#] devices are OFCI and only compatible with 3G-SDI Level B. Contractor shall provide (CFCI) conversion to/from Level A.**
21. The TSG-1-LIC is part of the TSG-1 in the specifications. On the BOM the TSG-1 is not listed, however the license TSG-1-LIC is listed in the BOM. Should we add a line for the TSG-1 that includes the TSG-1-LIC?
- a. [LCC Response] [TSG-1] is OFOI in the CAP, however the [TSG-1-LIC] has expired. Contractor shall procure and install a new [TSG-1-LIC] for the Owner's [TSG-1].**
22. What is the Master Control Automation System that currently provides playout scheduling? Does this need to integrate with the new MCWS-1 and associated layout resources?
- a. [LCC Response] There is no Master Control Automation System – playlists are manually played back and controlled via an operator.**
23. There are conflicts between the drawings and BOM as to which items are OFCI. Which document takes precedence?
- a. [LCC Response] See above and below. If additional discrepancies remain, submit additional RFIs for clarification.**
24. Is HLG HDR required end-to-end for all signal paths, or are SDR monitoring and editorial paths acceptable for certain destinations?
- a. [LCC Response] All video systems shall operate in the standard of 1920x1080p59.94, with a color space achieving ITU-R Recommendation BT.2100 (HDR HLG). (Refer to revised 27 41 16 Specifications Addendum 3, §2.03.A.1.a)**
25. Are there defined blackout periods (sessions, elections, special proceedings) during which outages and cutovers are prohibited and should be excluded from bidder schedules?
- a. [LCC Response] Outages and cutovers are prohibited during the regular legislative session per the Minnesota Legislature's official calendar. Bidders shall obtain current session dates from the LCC at award and incorporate them into the baseline schedule. Special sessions cannot be scheduled in advance and are infrequent. If one is called, the Contractor will coordinate with the LCC, FinePoint Technology, House Public Information Services, and Senate Media Services to accommodate the session. Special session accommodation is not anticipated to be a significant scheduling impact. The Capitol Office Building (COB) shall remain operational until the State Office Building (SOB) is complete and accepted by the LCC.**

26. Are there room-level availability milestones for SOB (control rooms, studio, rack rooms) for bid-level scheduling assumptions.
- a. [LCC Response] Contractor should assume all HPIS technical spaces will be ready no later than January 1<sup>st</sup> 2027.**
27. Can you provide drawings and equipment lists for phase 1 project and all equipment that will interface with phase 2?
- a. [LCC Response] Drawings and documentation from the Phase 1 project will be provided to the Contractor after contract award. Documents will be provided "for reference only" and will not be incorporated into this contract. The Drawings and Specifications for this RFP describe the interface requirements for Phase 1 owner-furnished equipment. (Refer to revised 27 41 16 Specifications Addendum 3, §2.04)**
28. Do EOL and discontinued items require submitting a substitution form?
- a. [LCC Response] EOL and discontinued items may be substituted with equivalent replacement parts, provided by the same manufacturer as a direct equivalent, so long as they continue to meet the specified criteria. All other substitutions will require an approved Substitution Request Form.**
29. Will the completion schedule be amended if construction of the SOB timeline gets extended?
- a. [LCC Response] Yes. The Contractor's completion schedule is tied to SOB construction milestones and building access. If the SOB construction timeline is extended by the State, the Contractor's schedule will be adjusted accordingly through a no-cost time extension. Schedule adjustments driven by SOB construction delays will not entitle the Contractor to additional compensation, extended general conditions, or escalation, except as required by law.**
30. Can you further define the inventory and asset tagging process? Who is responsible for compiling and printing the list and what information is added to the tagging? What items get tagged?
- a. [LCC Response] The Contractor is responsible for compiling and maintaining a complete equipment inventory list and submitting it as part of the project closeout documentation. The inventory shall include, at minimum:**
- **Manufacturer**
  - **Model number**
  - **Serial number**
  - **Equipment description**
  - **Room / location**
  - **LCC asset tag number (where applicable)**
- Any item with an individual unit value of \$500 or greater shall receive an LCC-provided asset tag. The LCC will furnish the tags to the Contractor; the Contractor is responsible for applying them to the equipment and recording the asset tag number against the corresponding inventory entry.**
- Tags shall be applied in a location that is accessible for future inventory audits but does not interfere with equipment operation, ventilation, or the finished aesthetic of installed end-points (e.g., on the rear or underside of devices, or on rack-mounted hardware where not visible).**
- Final inventory list shall be submitted in editable spreadsheet format (Excel or equivalent) prior to Substantial Completion.**
31. 27-41-16-Broadcast-System-Bill-of-Materials-Phase-2-v2-Addendum-2 Page 12 appears to be missing equipment when compared to Version 1. Please confirm final Broadcast System Bill of Materials.

- a. [LCC Response] Lines on page 12 were accidentally omitted in the addendum 2 version due to an export error. See revised Bill of Materials, addendum 3.*
32. B201.15 OFOI EQUIPMENT RACK PROVIDED AND INSTALLED BY AV CONTRACTOR. SPACE SET ASIDE FOR BROADCAST EQUIPMENT. COORDINATE WORK WITH AV CONTRACTOR. Just to confirm, is it Owner furnished and Owner installed or Owner furnished Contractor installed?
- a. [LCC Response] Equipment racks supporting the hearing rooms in the SOB are Owner-Furnished Owner-Installed racks and are provided and installed under separate contract with the base building. See [RACK-6]. (Refer to revised 27 41 16 Specifications Addendum 3, §2.08.B.1.a.6)*
33. For the Hitomi piece- we will need you to provide the Analyzer MAC address in order to provide a quote. Can you please provide that?
- a. [LCC Response] fc:0f:e7:2c:33:e5*
34. CAP B883 East Telco CATV Encoder/Modulator (OFOI) [MOD-1]1 OFOI  
CAP B883 East Telco CATV Encoder/Modulator (OFOI) [MOD-2]2 OFOI Are these HDMI input or SDI? If HDMI, they may require converters. If so, who is responsible to supply these, client or SI?
- a. [LCC Response] [MOD-1] and [MOD-2] have HD-SDI and SD-SDI inputs respectively. (Refer to revised 27 41 16 Specifications Addendum 3, §2.05.BB)*
35. The drawings, specifications, and BOM appear to reference [CONSOLE-W2] and [CONSOLE-W-1] as the same item. Are these the same, or different?
- a. Yes, these are the same worksurface. QTY 1 is required in SOB 0G125 Equipment Room. Assume all references to [CONSOLE-W2] and [CONSOLE-W-1] are equivalent.*

END OF ADDENDUM